



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

May 22, 2009

Addendum No. 3

TIP #: R-5134

WBS#: 45034.3.ST1

Martin County

Milling and Resurfacing on US 17 Business

To Whom It May Concern:

Reference is made to the contract proposal previously furnished for this project.

The following revision has been made to the proposal:

Page No. 32 has been revised to add the Special Provision "Removal of Existing Curb & Gutter and Sidewalk". Please void Page No. 33 in your proposal and staple the revised Page 33 thereto.

The Table of Contents has been revised to reflect the above mentioned revision. Please void the Table of Contents in your proposal and staple the revised Table of Contents thereto.

As a point of clarification, the item "Retrofit Existing Wheelchair Ramps" should be bid according to the requirements of Section 848 of the *Standard Specifications* and the Special Provision included in the proposal for this project.

Sincerely,

A handwritten signature in dark ink, appearing to read "W. B. Hobbs", with a stylized flourish at the end.

W. B. Hobbs, PE
Division Project Manager

WBH

Attachments

cc: J. D. Jennings, PE
D. S. Lee, PE

113 Airport Drive, Suite 100, Edenton, NC 27932, Phone (252)-482-7977, Fax (252)-482-8722

CONTENTS

STANDARD PROVISIONS

General	5
Bids	5
Availability of Funds - Contract Termination	5
Contract Payment and Performance Bond	5
Extension of Contract Time	5
Default of Contract	6
Subletting of Contract	6
Notification of Operations	6
Temporary Suspension of Work	6
Authority of the Engineer	6
Claims for Additional Compensation or Extension of Time	6
Bankruptcy	7
Partial Payment	7
Prompt Payment (Subcontractors)	7
Liability Insurance	8
Supervision by Contractor	8
Posted Weight Limits	9
Inspection	9
Materials and Testing	9
Erosion Control	9
Utility Conflicts	10
Safety and Accident Protection	10
Plan, Detail and Quantity Adjustments	10
Cooperation Between Contractors	10
Approval of Personnel	11
Outsourcing Outside The USA	11
Safety Vests	11

SPECIAL PROVISIONS

Notes To Contractor	12
Contract Time and Liquidated Damages	12
Intermediate Contract Time Number 1 and	
Liquidated Damages	12
Low Shoulder, Unmarked Pavement, Do Not Pass, Signs	13
Disadvantaged Business Enterprises	13
Prosecution of Work	19
Progress Schedule	20
Traffic Control	21
Construction Sequence	22
Workzone Signing	23
Asphalt Pavements-Superpave	24
Asphalt Binder Content Of Asphalt Plant Mixes	30
Asphalt Concrete Surface Course Compaction.	30
Fuel Price Adjustment	31
Price Adjustment - Asphalt Binder for Plant Mix	31
Paving Intersections, Driveways and Mailbox Turnouts	31
Asphalt Paver	31

SPECIAL PROVISIONS (cont'd)

Final Acceptance and Fourteen Day Observation Period	32
Variable Depth Milling	32
Major Contract Items	32
Adjustment of Meter Boxes or Valve Boxes	32
Adjustment Of Manholes	32
Removal of Existing Curb & Gutter and Sidewalk	32
Specialty Items	32A
Retrofit Existing Wheelchair Ramps	33
Removal of Existing Pavement Marker	33
Driveway and Private Property	34
Pavement Width Varies	34
Aggregate Production	34
Portland Cement Concrete (Alkali-Silica Reaction)	34
Borrow Excavation And SHPO Documentation For Borrow / Waste Sites	35
Pavement Marking Lines	35
Glass Beads	35
Roadway Standard Drawings For Pavement Markings and Markers	36
Time Limitation for Pavement Marking	36
ERRATA	37
Traffic Control (Lump Sum)	40
Required Contract Provision For ARRA	40
FHWA-1273	41
Revision to FHWA-1273 Concerning Personal Information On Payroll Submissions	53
Certification for Federal-Aid Contracts	53
U.S. Department of Transportation Hotline	53
Maintenance of the Project	54
Award of Contract	54
Minority and Female Employment Requirements	54
On the Job Training	56
Wage Rates	58
DBE Reporting Form	62
Execution of Bid, Non-Collusion Affidavit and Debarment Certification	63
Bid Form	72

FINAL ACCEPTANCE AND FOURTEEN DAY OBSERVATION PERIOD:

Upon completion of construction as shown on each map, a 14 day observation period is required before acceptance. During the 14-day period, warrant the resurfaced area against failure.

No payment will be made for replacing failed pavement, as the cost of it will be considered incidental to the work initially paid for under the various items in the contract.

Completion and final acceptance of the project is contingent upon successful completion of the Observation Period. The observation period will be considered a part of the work required to be completed by the final completion date specified herein.

VARIABLE DEPTH MILLING

On maps where asphalt has been placed in the gutter or where asphalt is higher than the gutter, mill asphalt pavement to a depth 1.5" below the top edge of the gutter. Establish a cross slope of 0.025 from that point back towards the center of the road. Milling depth will vary from 2" to 3". Remove asphalt from gutter where it exists.

All other provisions of section 607 of the Standard Specifications shall apply.

Pay Item	Pay Unit
Variable Depth Milling	Square Yard

MAJOR CONTRACT ITEMS

The following listed items are the major contract items for this contract (See Articles 101 and 104-5 of the *2006 Standard Specifications*):

Line #	Description
3	Asphalt Concrete Surface Course, Type S9.5B

ADJUSTMENT OF METER BOXES OR VALVE BOXES

The Contractor shall adjust, raise or lower, all existing valve boxes, manholes, and meter boxes within the construction limits of the project in accordance with Section 858 of the Standard Specifications. Payment will be made under "Adjustment of Valve Boxes" per each.

ADJUSTMENT TO MANHOLES

The Contractor's attention is directed to Section 858-3 of the *2006 Standard Specifications*. Make adjustments to manholes on this project by using rings or rapid set, (grout, mortar, or concrete) as approved by the Engineer.

REMOVAL OF EXISTING CURB & GUTTER AND SIDEWALK

The quantities of 2'6" concrete curb and gutter 4" concrete sidewalk in this project are included to replace existing curb and gutter and sidewalk. Removal and disposal of existing curb and gutter and sidewalk will be considered incidental to the other bid items on this project. No additional compensation will be made for removal and disposal of existing curb and gutter and sidewalk.