



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

August 01, 2011

PROJECT: B-5205
COUNTY: Beaufort
ROUTE: Replace Bridge #139 on SR 1626

ADDENDUM NUMBER 1

TO: Prospective Bidders

Please note the following revision to the contract proposal for the above-referenced project.

Replace line item #34

34	1630	SILT EXCAVATION	320	LF		
----	------	-----------------	-----	----	--	--

With

34	1630	SILT EXCAVATION	5	CY		
----	------	-----------------	---	----	--	--

A revised bid sheet has been included. Please replace the original sheet.

If you should have any questions concerning this, please call me at (252) 695-2044.

Sincerely,

Lang Jones
Division DDC Engineer

29	1620	SEED FOR TEMPORARY SEEDING	50	LB		
30	1620	FERTILIZER FOR TEMP. SEEDING	0.2	TON		
31	1622	TEMPORARY SLOPE DRAINS	200	LF		
32	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA		
33	SP	SAFETY FENCE	320	LF		
34	1630	SILT EXCAVATION	5	CY		
35	1631	MATTING FOR EROSION CONTROL	535	SY		
36	1632	¼" HARDWARE CLOTH	160	LF		
37	SP	FLOATING TURBIDITY CURTAIN	80	SY		
38	1660	SEEDING AND MULCHING	1	ACR		
39	1661	SEED FOR REPAIR SEEDING	50	LB		
40	1661	FERTILIZER FOR REPAIR SEEDING	0.2	TON		
41	402	REMOVAL OF EXISTING STRUCTURE AT -L- STA 23+00	1	LS		
42	412	UNCLASSIFIED STRUCTURE EXCAVATION	1	LS		
43	420	CLASS AA CONCRETE (BRIDGE)	53.4	CY		
44	422	BRIDGE APPROACH SLABS	1	LS		
45	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	8990	LB		
46	450	HP 12X53 GALVANIZED STEEL PILES	650	LF		
47	450	HP 14X73 GALVANIZED STEEL PILES	1050	LF		
48	450	PILE REDRIVES	14	EA		
49	SP	VERTICAL CONCRETE BARRIER RAIL	220.87	LF		
50	430	ELASTOMETRIC BEARINGS	1	LS		
51	430	3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLABS	1100	LF		

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____

ADDRESS _____

Federal Identification Number _____ Contractors License Number _____

Authorized Agent _____ Title _____

Signature _____ Date _____

Witness _____ Title _____

Signature _____ Date _____