



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

October 10, 2011

PROJECT: 34608.2.3
COUNTIES: Beaufort, Carteret, Craven, Greene, Jones, Lenoir, Pamlico, Pitt
ROUTE: Various
DESCRIPTION: Division-wide Installation of Hot-Spray Thermoplastic, Hot-Extruded
Thermoplastic, and Polyurea Pavement Markings
ADDENDUM NUMBER 3

TO: Prospective Bidders

Please note the following revisions to the contract proposal for the above-referenced project.

- Insert Page 18A, clarifying requirements and payment for site preparation and removal of pavement marking lines.
- The Bid Form has been revised reflecting corrected quantities for Items 9 and 10. **Original version of the Bid Form with incorrect quantities will not be accepted.**

The remainder of the proposal document is unaffected. If you should have any questions concerning this addendum, please call me at (252) 695-2044.

Sincerely,

A handwritten signature in black ink, appearing to read "A Bullard".

Aaron Bullard, PE
Division Contract Officer

Attachments

cc: Mr. Steve Hamilton, PE

SITE PREPARATION / REMOVAL OF PAVEMENT MARKING LINES:

The pavement surface shall be prepared to accept pavement markings in accordance with Articles 1205-3(F) and 1205-3(I) of the *Standard Specifications*.

For installation of Hot-Spray Thermoplastic markings, removal of the existing lines is not expected to represent the typical method of preparation. Surface preparation shall be considered incidental to the Hot-Spray Thermoplastic application and shall be included in the pay item for installation of the Hot-Spray Thermoplastic markings.

Installation of Hot-Extruded Thermoplastic and Polyurea markings may require removal of existing pavement marking lines in accordance with Article 1205-3(I), and payment for this removal will be paid for as specified in Article 1205-10.

North Carolina Department of Transportation

BID FORM

WBS ELEMENT: 34608.2.3
ROUTE: Various
COUNTIES: Beaufort, Carteret, Craven, Greene, Jones, Lenoir, Pamlico, Pitt
DESCRIPTION: Division-wide Installation of Hot-Spray Thermoplastic, Hot-Extruded Thermoplastic, and Polyurea Pavement Markings

BID OPENING: October 25, 2011 @ 11:00 AM

ITEM	SECT	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
1	1205	HOT-SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4")	2,000,000	LF		
2	1205	HOT-SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (6")	100,000	LF		
3	1205	HOT-EXTRUDED THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	50,000	LF		
4	1205	HOT-EXTRUDED THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	50,000	LF		
5	1205	HOT-EXTRUDED THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	100,000	LF		
6	1205	HOT-EXTRUDED THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	100,000	LF		
7	1205	POLYUREA PAVEMENT MARKING LINES (6")	50,000	LF		
8	1205	POLYUREA PAVEMENT MARKING LINES, (4")	50,000	LF		
9	1205	REMOVAL OF PAVEMENT MARKING LINES, (4")	150,000	LF		
10	1205	REMOVAL OF PAVEMENT MARKING LINES, (6")	250,000	LF		

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____

ADDRESS _____
