

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

ADDENDUM NO. 3

2 August 2011

Re: Burgaw QA Lab Office Renovation

ID# 11-08685-01A

PREPARED BY: Facilities Design, NCDOT

The following clarifications, changes, additions and/or deducts shall be made to the Working Drawings and Specifications. These changes shall be included in the Contract Amount for the Construction Work as indicated below:

Specification .:

Item No. Page No. Description:

1. Gen. Cond. Invoices for Payment: Three (3) monthly partial payments are expected before

the Final Payment for this 90 consecutive calendar day construction project.

Drawings:

Item No. Sheet No. Description:

1. A1 Plan D6A1: Disregard "Drainage Pipe Below New Sidewalk"; slope subgrade and

new gravel away from the building towards the new sidewalks for positive drainage.

(E0.1, ED0.1) Add to General Notes item 10. Gable end Transite shingle siding conduit

penetrations shall be reused as noted in Addendum No. 1 (<5% assumed asbestos containing). See New Riser on sheet E0.1 and Partial Demo Riser on sheet ED0.1.

(A3) Existing 12x12 ceiling tile is noted in the Asbestos Inspection Report as "No

Asbestos Detected".

2. A2 Countertops: Substitute Plastic Laminate for Stainless Steel countertops equal to

WilsonArt #4762-60, "Mystique Mount" or Nevamar or Formica as indicated on Sections D6A2, D4A2, and B6A2 (plastic laminate is correctly shown on the

elevations).

Vic Buzard, RA, NCDOT / John McNally, PE, MCBH / Allen Cribb, PE, MCBH

cc: http://www.ncdot.org/doh/operations/division3/ (for Bidders at the NCDOT Division 3 web site) SCO

MAILING ADDRESS: NC DEPARTMENT OF TRANSPORTATION GENERAL SERVICES DIVISION 1525 MAIL SERVICE CENTER RALEIGH NC 27699-1525 TELEPHONE: 919-715-0400 FAX: 919-715-0399

WEBSITE: WWW.NCDOT.ORG

LOCATION: TRANSPORTATION BUILDING 1 SOUTH WILMINGTON STREET RALEIGH NC