PROJECT SPOTLIGHT

I-40 Widening From Harrison Avenue to East of Jones Franklin Road in Wake County (I-4744) Jonathan Bivens, PE V.P. Engineering/Design-Build S. T. Wooten Corporation

Dennis Jernigan, PE
Division Construction Engineer
NCDOT






Why Is This Project Needed?

- 160,000 ADT
- Four-lane section

- Max. Capacity of 4-lane @ LOS F w/ speed reductions is 72,000 ADT
- The only four-lane section between US 15-501 and US 70 Business (Wake & Durham Counties)
- Major artery into & out of RTP, Raleigh, Durham and Chapel Hill
- Number 1 CAMPO priority project
- Peak hour & holiday traffic jams



Design Considerations/Challenges

- Depth of temp. shoulder widening 13.5" to 16"
- Effect of trucks on temp. widening (6% duals, 12% TTST)
- Pavement type (asphalt vs. concrete)
- WZTC issues traffic management
- Broken down/abandoned vehicles
- Thin pavement marathon weekend
- Wade Avenue bridge movement








Design Considerations/Challenges

- Depth of temp. shoulder widening 13.5" to 16"
- Effect of trucks on temp. widening (6% duals, 12% TTST)
- Pavement type (asphalt vs. concrete)
- WZTC issues traffic management
- Broken down/abandoned vehicles
- Thin pavement marathon weekend
- Wade Avenue bridge movement

- Subsurface drainage
- Median access for construction
- Bridge foundations at Wade Avenue & US 1/64
- 34.5" permanent pavement
- Stabilization
- Elimination of US 1/64 freeflow on I-40 eastbound
- Other nearby projects tie-ins
- Events: RBC, Carter-Finley (Hurricanes), etc.

Project & Nearby Concerns



Design Considerations/Challenges

- Depth of temp. shoulder widening 13.5" to 16"
- Effect of trucks on temp. widening (6% duals, 12% TTST)
- Pavement type (asphalt vs. concrete)
- WZTC issues traffic management
- Broken down/abandoned vehicles
- Thin pavement marathon weekend
- Wade Avenue bridge movement

- Subsurface drainage
- Median access for construction
- Bridge foundations at Wade Avenue & US 1/64
- 34.5" permanent pavement
- Stabilization
- Elimination of US 1/64 freeflow on I-40 eastbound
- Other nearby projects tie-ins
- Events: RBC, Carter-Finley (Hurricanes), etc.
- High profile
- Needed a \$50 million project with little impact to motorists

S.T.Wooten Design/Build Team

-Experienced team

-RK&K – Lead Designer

-T&H Electrical-Dedicated Sub


Design/Build Solutions

- -PreBid Geotech Investigation
 - -Warm Mix Asphalt
 - -Material Conveyors
 - -Construction Planning














Paths To Resolution - Solutions















Every problem has in it the seeds of its own solution. If you don't have any problems, you don't get any seeds.

~Norman Vincent Peale

Hauling Hours

- Contract Restrictions
 - Single Vehicle
 - 6am to 9am Monday through Friday
 - 3pm to 8pm Monday through Friday
 - Multiple Vehicle
 - 6am to 9pm Monday Through Friday
 - 9am to 9pm Saturday
 - 10am to 9pm Sunday

Hauling Hours

- DB Team conducted a traffic study
- Study did not support full weekend hauling
- Study showed that hauling hours could be extended M-F starting at 7pm and beginning at 5pm Saturday
- NCDOT reviewed and accepted study, but was not comfortable extending Friday and weekend hauling hours
- Used a two-week trial period to determine impact of additional haul hours
- \$50K project credit

Hauling Hours

- Contract Restrictions
 - Single Vehicle
 - 6am to 9am Monday through Friday
 - 3pm to 8pm Monday through Friday
 - Multiple Vehicle
 - 6am to 7pm Monday Through Thursday
 - 9am to 9pm Saturday
 - 10am to 9pm Sunday



Traffic Control Meetings

- -established in addition to construction meetings
- -involved RK&K, NCDOT TC and Public Information, and construction team
- -discussed and reviewed upcoming work and impact to traffic
- -revised and improved MOT

54" CMP/Drilled Shaft Conflict

- Next-to-last shaft at Wade Avenue
- Pipe is shown on the plans
- Pipe was ~32' deep
- Drill brought up pieces of pipe








54" CMP/Drilled Shaft Conflict

- Next-to-last shaft at Wade Avenue
- Pipe shown on plans
- Pipe was ~32' deep
- Drill brought up pieces of pipe
- Casing used sealed it off
- Investigated with a pipe camera
- Specialized sub lined the pipe & pulled caisson at the same time

54" CMP/Drilled Shaft Conflict Resolution

- Drilled two extra shafts, one on each side of pipe
- Poured a footer on the two shafts to bridge the pipe



Sequence & Timeline

- 01/22/10 Coastal Caisson hit 54" pipe
- 02/09/10 Formal Repair procedure submitted to NCDOT
- 02/11/10 Hydraulics approval
- 02/15/10 Permit mod, submitted to NCDOT
- 02/15/10 Revised foundation recs. and substructure plans submitted to NCDOT
- 02/18/10 NCDOT approves revised foundation recs. and substructure plans
- 02/19/10 Permit mod. approved by NCDENR/DWQ
- 02/22-3/2/10 Pipe repair performed



Coordination

- High Traffic Levels
- Close Working Quarters
- Coordination with Adjacent Projects,
 Traffic Operations Center, and Emergency
 Organizations









Claim

Project Successes

- DB Team used technology to develop a plan that we could not specify in a design-bid-build
- Timely resolution of issues (started with weekly meetings); ABC gradation, etc.
- Early installation of lighting
- Traffic control monthly meetings
- No serious accidents/injuries Traffic feedback
- Traffic study information
- 40% ahead of schedule

Questions?