1.0 GENERAL

barrier rail shall be in accordance with the Standard Specifications, details shown the contract plans, and this Special Provision. Plans for the concrete barrier rail are detailed for slip-formed cast-in-place concrete. Concrete for the concrete barrier rail may be placed using either conventional forms or by the use of an approved self-propelled extrusion machine.

Basis of Payment

The quantity for which payment is made will be that quantity shown in linear feet on the paid for will be the quantity shown on the revised plans. Reinforcing steel and Class AA plans for "Concrete Barrier Rail". Where the plans have been revised, the quantity to be concrete contained in the concrete barrier rail is listed in a "Bill of Material for Concrete Barrier Rail" on the plans, and no separate measurement or payment will be made for these The unit bid per linear foot shall be full compensation for all materials, quantities. admixtures, forms, falsework, curing, surface finish, tools, labor, equipment and incidentals necessary to complete this item.