PUBLIC MEETING MAP

PROJECT 34817.1.FR7 (U–2519BA)
F.A. PROJECT NHF–0100(24)
PROJECT 34817.1.FR8 (U–2519BB)
F.A. PROJECT NHF–0100(25)
CUMBERLAND COUNTY
FAYETTEVILLE OUTER LOOP FROM SOUTH OF SR 1003 (CAMDEN ROAD) TO SOUTH OF US 401

PRELIMINARY PLANS — DO NOT USE FOR CONSTRUCTION

INCOMPLETE PLANS — DO NOT USE FOR R/W ACQUISITION

NC ONEMAP PHOTO — Download Date: FALL 2015

NOTE:
FULL CONTROL OF ACCESS IS DEFINED AS A CONNECTION TO A FACILITY PROVIDED ONLY VIA RAMPS AT INTERCHANGES. ALL CROSS-STREETS ARE GRADE-SEPERATED. NO PRIVATE DRIVEWAY CONNECTIONS ARE ALLOWED.

–L–

Pls Sta 469+90.00
Rθ = 9° 51' 01.9"
Le = 500.00'
LT = 200.00'
ST = 100.0'

PI Sta 483+41.99
Δ = 35° 29' 05.8" (RT)
D = 1° 30' 01.9"
L = 3,765.27'
T = 1,919.9'
R = 3,820.00'
SE = 0.06
V = 70 mph

Pls Sta 495+55.30
Rθ = 2° 15' 03.5"
Le = 500.00'
LT = 200.00'
ST = 100.0'

Pls Sta 510+25.55
Rθ = 2° 14' 59.4"
Le = 500.00'
LT = 200.00'
ST = 100.0'

Pls Sta 523+30.69
Δ = 35° 29' 13" (LT)
D = 1° 29' 59.8"
L = 3,764.82'
T = 1,905.1'
R = 3,820.00'
Vd = 70 MPH
SUPER = 6%

Pls Sta 535+60.37
Rθ = 2° 14' 59.4"
Le = 500.00'
LT = 200.00'
ST = 100.0'

–Y1T–

Pls Sta 15+19.42
Rθ = 12° 40' 29.8"
Le = 90.00'
LT = 60.00'
ST = 30.00'

PI Sta 20+90.05
Δ = 11° 09' 30.8" (RT)
D = 1° 29' 59.8"
L = 1,274.54'
T = 641.5'
R = 3,820.00'
Vd = 50 MPH
SUPER = 3%

Pls Sta 28+54.53
Rθ = 12° 40' 29.8"
Le = 90.00'
LT = 60.00'
ST = 30.00'

Pls Sta 37+42.82
Δ = 11° 09' 30.8" (RT)
D = 1° 29' 59.8"
L = 1,274.54'
T = 641.5'
R = 3,820.00'
Vd = 50 MPH
SUPER = 3%

PI Sta 95+42.78
Δ = 46° 49' 05.2" (RT)
D = 3° 49' 11.2"
L = 1,364.61'
T = 725.99'
R = 1,500.00'
Vd = 50 MPH
SUPER = 4%

PI Sta 95+43.79
Δ = 46° 49' 05.2" (RT)
D = 3° 49' 11.2"
L = 1,364.61'
T = 725.99'
R = 1,500.00'
Vd = 50 MPH
SUPER = 4%

Pls Sta 102+55.43
Rθ = 3° 17' 37.1"
Le = 150.00'
LT = 120.0'
ST = 64.02'