FINAL BRIDGING DECISIONS AND ALIGNMENT REVIEW

From US 25 in Hendersonville in Henderson County to I-40/I-240 in Buncombe County

Henderson and Buncombe Counties

STIP Project I-4400/I-4700

North Carolina Department of Transportation



MERGER CONCURRENCE POINT 2A

February 11, 2015

TABLE OF CONTENTS

Section	Page
1. INTRODUCTION	1
1.1 PROJECT BACKGROUND	1
1.2 PROJECT SCHEDULE	1
2. MERGER TEAM CONCURRENCES TO DATE	6
2.1 CONCURRENCE POINT 1: Project Purpose and Need	6
2.2 CONCURRENCE POINT 2: Preliminary Alternatives to be Studied in Detail	6
3. MERGER CONCURRENCE POINT 2A - Bridging Decisions and Alignment Review	7
3.1 EXISTING DRAINAGE CROSSINGS	7
3.2 DRAINAGE STRUCTURE RECOMMENDATIONS	7
4. MERGER PROJECT TEAM AGREEMENT SIGNATURE FORM	9
<u>Tables</u>	Page
Table 1: Recommended Major Drainage Structures	8
<u>Figures</u>	Page
Figure 1-1: Project Vicinity	2
Figures 1-2A through 1-2C: Project Study Area	3, 4, 5
Appendices	
Appendix A: Typical Roadway Sections	

Merger Concurrence Point 2A STIP Project: I-4400/I-4700

Appendix B: Site Maps and Photographs

1. INTRODUCTION

The North Carolina Department of Transportation (NCDOT), in cooperation with the Federal Highway Administration (FHWA), proposes transportation improvements to a segment of the I-26 corridor from US 25 in Henderson County, north to I-40 in Buncombe County. This document is intended to include the information necessary for Merger Team members to make a determination for Concurrence Point 2A: Bridging Decisions and Alignment Review. As such, this document includes the following sections: 1) Introduction, 2) Merger Team Concurrences to Date, 3) Merger Concurrence Point 2A – Bridging Decisions and Alignment Review, and 4) Merger Project Team Agreement Signature Form.

1.1 PROJECT BACKGROUND

1.1.1 Project Setting

The project is located in northern Henderson County, just south of Hendersonville, and southern Buncombe County, just south of Asheville. **Figure 1-1** shows the general project vicinity. The Town of Fletcher is also in the nearby vicinity. The project study area boundaries consist of a generally 1,400ft wide corridor that follows existing I-26 along its footprint from US 25 in Henderson County, north to I-40 in Buncombe County. Expanded study areas have been included around interchanges incorporated into the I-26 project study as well as expanded study area around the Blue Ridge Parkway bridge, which has also been included in the project study. **Figures 1-2A, 1-2B**, and **1-2C** illustrate the project study area.


1.1.2 Project History


An Environmental Assessment was completed for STIP I-4400 (the 13.6 mile segment between US 25 and NC 280) in May 2001. A Finding of No Significant Impact was completed in January 2002 and, subsequently, the project was advertised as a Design-Build project by NCDOT. A lawsuit and resulting judgment in 2003 found that NCDOT should conduct a broader analysis of the cumulative impacts and logical termini, or project limits, of the overall expansion of the I-26 corridor. The project was subsequently placed on hold due to financial constraints. However, the growing need for improvements to the I-26 corridor was recognized and the project was reinitiated and included in the Draft NCDOT 2013-2023 STIP. In order to address the 2003 judgment, the NCDOT concluded to combine the analysis of STIP I-4400 with STIP I-4700 (the 8.6-mile segment between NC 280 and I-40) into one comprehensive Environmental Impact Statement (EIS). The EIS will address logical termini and cumulative effects in accordance with NEPA.


1.2 PROJECT SCHEDULE


The following bullets outline the tentative project schedule. These major milestone target dates are preliminary and subject to change.

•	Project Technical Reports	2013 – 2015
•	Draft Environmental Impact Statement	Late 2015
•	Public Hearing	2016
•	Final Environmental Impact Statement	Late 2016
•	Record of Decision	2017
•	Begin Right-of-Way Acquisition	2018
•	Begin Construction	2020









1.1.3 Public Involvement

The project was reinitiated in late 2012. Public comment was solicited at the first Citizens Informational Workshop held in January 2013. The consensus of the comments was in favor and support of the project and the expectation that the improvements and widening of I-26 in the project study area would facilitate improved traffic flow in the area. An additional Citizens Informational Workshop to gather further public input on detailed study alternatives is anticipated, as well as a Public Hearing after preparation of the Draft EIS.

2. MERGER TEAM CONCURRENCES TO DATE

2.1 CONCURRENCE POINT 1: Project Purpose And Need

The Project Team concurred on the following Purpose and Need Statement on June 20, 2013:

The needs to be addressed by this project include:

- Improve existing and projected roadway capacity deficiencies.
- Improve insufficient pavement structure and deteriorating existing road surface conditions.

The purpose of the proposed improvements to I-26, from US 25 in Henderson County north to I-40 in Buncombe County, is to reduce congestion, with a goal of achieving an overall LOS D in the design year (2040), and improve the pavement structure.

2.2 CONCURRENCE POINT 2: Preliminary Alternatives To Be Studied In Detail

On June 20, 2013, the Project Team also concurred on the following alternatives to be carried forward:

<u>Build Alternative 1 – "Best Fit" 6-Lane Widening Alternative</u>: Alternative 1 would widen I-26 along the full project corridor to a 6-lane facility asymmetrically at locations that "best fit" the current roadway location and surrounding land uses. "Best Fit" locations will be evaluated and selected to improve the existing highway alignment, minimize impacts, and accommodate maintenance of traffic during construction.

<u>Build Alternative 2 – "Best Fit" 8-Lane Widening Alternative</u>: Alternative 2 would widen I-26 along the full project corridor to an 8-lane facility asymmetrically at locations that "best fit" the current roadway location and surrounding land uses. "Best Fit" locations will be evaluated and selected to improve the existing highway alignment, minimize impacts, and accommodate maintenance of traffic during construction.

<u>Build Alternative 3 – "Best Fit" Traffic Report Recommendations Widening Alternative:</u>
Alternative 3 would widen I-26 as a hybrid of 6- or 8-lane segments at different locations along the project corridor. Widening to 6- or 8-lanes will be asymmetrical at locations that "best fit" the current roadway location and surrounding land uses and as outlined in the traffic report recommendations in specific areas. "Best Fit" locations will be evaluated and selected to improve the existing highway alignment, minimize impacts, and accommodate maintenance of traffic during construction. Build Alternative 3 is also referred to as the Hybrid 6-/8-Lane Widening Alternative.

Typical roadway sections are included in **Appendix A**.

3. MERGER CONCURRENCE POINT 2A - Bridging Decisions and Alignment Review

3.1 EXISTING DRAINAGE CROSSINGS

Local land use plans for the study area and the Natural Resources Technical Report (NCDOT, August 2014) prepared for the project indicate that the contributing drainage areas are predominantly urban in nature and will continue to be so at build out. Most streams in the study area drain areas less than five acres, including seven streams that drain less than one acre. There are no known flooding issues associated with any of the studied crossings.

Field investigations and preliminary hydraulic studies (Hydraulic Technical Memorandum, HNTB, May 2014 and Addendum to Hydraulic Technical Memorandum, HNTB, November 2014) were conducted for 28 stream crossings in the project corridor. Of these, four are bridges, 15 are major culvert crossings (conveyance greater than or equal to a 72-inch pipe), and nine are 66-inch pipes. One of the 66-inch pipes is combined with a 14' x 14' vehicle underpass that also allows flows under I-26. The other 66-inch crossings were determined not to require a conveyance equal to or greater than a 72-inch pipe; therefore, these crossings are not addressed in this review (Sites 5, 6, 8, 9, 15, 20, 21, and 22). In addition, it was determined that several sites in proximity to the project termini are no longer within the project limits and are not addressed in this review (Sites 1, 2, 27, and 28).

Drainage structure recommendations for the remaining 16 sites are provided. Of the 16 crossings evaluated, seven are located on FEMA-studied streams. All of these crossings are within the French Broad River Basin and there is no requirement for riparian buffers. Site location maps and photographs of the stream crossings and existing structures are included in **Appendix B**.

3.2 DRAINAGE STRUCTURE RECOMMENDATIONS

Based on the hydrologic analysis, no change to the type of existing structures is warranted. It is recommended that all existing bridges be removed and replaced. Similarly, existing culverts are recommended to be retained and extended. Supplemental pipes are recommended in some locations. Specific drainage structure recommendations are shown in **Table 1**.

Although some streams and one wetland would be impacted by the culvert extensions, it is not recommended that any culverts be replaced with bridges. For an existing interstate project, it is generally not feasible or practicable to replace existing culverts with bridges, primarily due to cost and constructability issues. Replacing an existing culvert with a bridge would require several construction steps beyond what would be necessary to extend an existing culvert and/or provide a supplemental overflow pipe. The initial step involves construction of an on-site detour (likely outside the existing roadway footprint resulting in increased impacts) to maintain traffic. Once the on-site detour is complete, traffic would shift to the detour to allow for excavation of the existing roadbed and culvert. It is anticipated that temporary stream channels and a phased removal of the existing culvert would be necessary to maintain the flow in the existing stream. Upon the removal of the culvert, the new bridge would be constructed. Finally, traffic would be shifted to the completed bridge and the on-site detour removed. In most cases, the impacts associated with the on-site detour and the temporary stream channels would increase the impacts associated with a simple culvert extension or supplement.

Costs for recommended culvert extensions, supplemental pipes, and bridges are included in **Table 1**. For comparison, costs to replace existing culverts with bridges were estimated. This cost comparison highlights the substantial increase in cost to replace an existing culvert with a bridge.

Table 1. Recommended Major Drainage Structures

			STREAM INFORMATION					EXISTING STRUCTURE	6-LAN	NE WIDENING		8-LANE WIDENING			HYBRID 6-/8-LANE WIDENING				
SITE NUMBER	STATION	ROUTE	STREAM NAME	NRTR MAP ID	NCDWR STREAM INDEX NUMBER	PERENNIAL / INTERMITTENT	STREAM LENGTH (ft)	STREAM CLASS	DRAINAGE AREA (sq mi) [acres]	Number, Size, Structure Type (Existing Length)	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (If)/ Wetland (ac) Impact	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (If)/ Wetland (ac) Impact	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (If)/ Wetland (ac) Impact
3	-L- 79+09	I-26	UT to Dunn Creek	SV	6-55-8-1- 1	Р	725	С	0.28 178	1 @ 6' x 6' RCBC (240')	Retain and extend (18' [RT]/47' [LT])	\$ 55,000 (\$1,223,000)	145/0	Retain and extend (25' [RT]/27' [LT])	\$ 44,000 (\$1,458,000)	132/0	Retain and extend (18' [RT]/47' [LT])	\$ 55,000 (\$1,223,000)	145/0
4	-L- 90+32	I-26	Dunn Creek	ST	6-55-8-1- 1	Р	845	С	2.58 1,649	2 @ 8' x 8' RCBC (354')	Retain existing; add supplemental pipe	\$248,000 (\$1,151,000)	0/0	Retain and extend; add supplemental pipe (45' [RT]/18' [LT])	\$382,000 (1,327,000)	143/0	Retain existing; add supplemental pipe	\$248,000 (\$1,151,000)	0/0
7	-L- 208+70	I-26	Devils Fork	SAJ	6-55-8-2	Р	2849	С	6.80 4,351	3 @ 9' X 10' RCBC (220')	Retain and extend (42' [RT]/20' [LT])	\$177,000 (1,295,000)	142/0	Retain and extend (42' [RT]/70' [LT])	\$320,000 (\$1,544,000)	192/0	Retain and extend (42' [RT]/20' [LT])	\$177,000 (1,295,000)	142/0
10	-L- 248+18	I-26	UT to Devils Fork	SAR	6-55-8-2	Р	812	С	0.29 185	1 @ 6' x 6' RCBC (382')	Retain existing	0	0/0	Retain and extend (0' [RT]/8' [LT])	\$ 7,000 (\$1,372,000)	48/0	Retain existing	0	0/0
11	-L- 334+69	I-26	Clear Creek	SBD	6-55-11- (5)	Р	908	С	44.30 28,352	Dual 3 - Span RC Deck Bridges; L = 220.14'	Remove and replace; L (Min) = 230'	(3,227,000)	-	Remove and replace; L (Min) = 230'	(3,862,000)	-	Remove and replace; L (Min) = 230'	(3,227,000)	-
12	-L- 407+69	I-26	UT to Mud Creek	SBG	6-55	Р	1,433	С	0.46 296	1 @ 7' x 7' RCBC (266')	Retain and extend (18' [RT]/0'[LT])	\$ 18,000 (\$2,086,000)	58/0	Retain and extend (26' [RT]/18' [LT])	\$ 44,000 (\$2,486,000)	124/0	Retain and extend (18' [RT]/0'[LT])	\$ 18,000 (\$2,086,000)	58/0
13	-L- 438+81	I-26	Featherstone Creek	SBP	6-55-12	Р	643	С	4.09 2,616	3 @ 8' x 8' RCBC (160')	Retain existing	0	0/0	Retain and extend; add supplemental pipe (32' [RT]/52' [LT])	\$351,000 (\$943,000)	164/0	Retain existing	0	0/0
14	-L- 500+94	I-26	Byers Creek	SBU	6-55-13	Р	1219	С	2.42 1,550	2 @ 8' x 8' RCBC (156')	Retain and extend; add supplemental pipe (21' [RT]/16' [LT])	\$196,000 (\$720,000)	117/0	Retain and extend; add supplemental pipe (33' [RT]/28' [LT])	\$260,000 (4858,000)	141/0	Retain and extend; add supplemental pipe (21' [RT]/16' [LT])	\$196,000 (\$720,000)	117/0
16	-L- 669+02	I-26	Cane Creek	SCW	6-57-(9)	Р	878	С	83.80 53,632	Dual 3 - Span RC Deck Bridges; L = 198.25'	Remove and replace; L (Min) = 210'	(2,947,000)	-	Remove and replace; L (Min) = 210'	3,526,000	-	Remove and replace; L (Min) = 210'	(3,526,000)	-
17	-L- 682+68	I-26	Kimsey Creek	SCY	6-57-22	Р	960	С	2.49 1,594	3 @ 7' x 7' RCBC (236')	Retain and extend; add supplemental pipe (20' [RT]/30' [LT])	\$287,000 (\$1,511,000)	130/0	Retain and extend; add supplemental pipe (36' [RT]/48' [LT])	\$396,000 (\$1,801,000)	164/0	Retain and extend; add supplemental pipe (36' [RT]/48' [LT])	\$396,000 (\$1,801,000)	164/0
18	-Y12- 11+44	SR 135 8	UT to French Broad River	-	6-(54.5)	-	-	В	0.14 88	1 @ 6' x 5' RCBC - 66" RCP w/ HW (540')	Retain existing	0	0/0	Retain and extend (0' [RT]/8' [LT])	\$7,000	48/0	Retain and extend (0' [RT]/8' [LT])	\$7,000	48/0
19	-L- 800+81	I-26	UT to French Broad River	SDC	6-(54.5)	Р	961	В	0.36 228	1 @ 6' x 6' RCBC (220')	Retain and extend; add supplemental pipe (22' [RT]/27' [LT])	\$233,000 (\$1,583,000)	129/0	Retain and extend; add supplemental pipe (48' [RT]/27' [LT])	\$262,000 (\$1,886,000)	155/0	Retain and extend; add supplemental pipe (48' [RT]/27' [LT])	\$262,000 (\$1,886,000)	155/0
23	-L47001- 897+06	I-26	Powell Creek	SDN	6-62	Р	470	С	5.06 3,240	2 @ 10' x 10' RCBC (264')	Retain and extend (28' [RT]/0' [LT])	\$ 68,000 (\$1,655,000)	68/0	Retain and extend (80' [RT]/24' [LT])	\$250,000 (\$1,972,000)	184/0	Retain and extend (80' [RT]/24' [LT])	\$250,000 (\$1,972,000)	184/0
24	-L47001- 931+91	I-26	Ducker Creek	SDT	6-63	Р	377	С	0.99 632	1 @ 8' x 8' RCBC (552')	Retain existing	0	0/0	Retain existing	0	0/0	Retain existing	0	0/0
25	-L47002- 1076+40	I-26	French Broad River		6-(54.5)			В	678.00 433,920	Dual 6 - Span RC Deck Bridges; L1 = 440.9' L2 = 453.4'	Remove and replace; L (Min) = 460'	(\$6,454,000)	-	Remove and replace; L (Min) = 460'	\$7,724,000	-	Remove and replace; L (Min) = 460'	(\$7,724,000)	-
26	-L47002- 1151+85	I-26	Long Valley Branch	SFN	6-75	Р	44	С	0.25 158	1 @ 66" SPP w/ HW; 1 @ 14' x 14' RCBC [vehicle underpass] (220')	Retain existing	0	0/0	Retain and extend (20' [RT]/40' [LT])	\$118,000 (\$2,315,000)	140/0.25	Retain and extend (20' [RT]/40' [LT])	\$118,000 (\$2,315,000)	140/0.25

NOTES: Minimum supplemental pipe size is 48".

Stream/wetland impacts are measured from the openings of the existing culverts to 40 feet beyond slope stakes.

For comparison, costs to replace existing culverts with bridges were estimated for sites where culvert extensions would be needed. Contour mapping was used to estimate the length of bridges at sites with existing culverts. Cost estimates are based on unit costs and bid averages provided by NCDOT.

Unit costs

Culvert: single -\$35/sf, double - \$30/sf, triple - \$25/sf

Bridges: \$115/sf

48" Supplemental Pipe: \$620/If (bore and jack)

Stream mitigation is not included in the culvert extension costs. However, a 2:1 mitigation ratio would result in an increase in the culvert extension costs by \$762/If.

Site 18 is outside the NRTR boundary.

Wetlands are present only at Site 26.

4. MERGER PROJECT TEAM AGREEMENT SIGNATURE FORM

Merger Project Team Agreement

Concurrence Point 2A: Bridging Decisions and Alignment Review

Project Name/Description:
I-26, Widen from US 25 in Hendersonville in Henderson County to
I-40/I-240 in Buncombe County
TIP Project: I-4400/I-4700

Bridging Decisions: Based on the current preliminary hydraulics design for the existing major drainage structures for TIP Project I-4400/I-4700, the proposed culvert and bridging recommendations are presented in the following table:

SITE	PROPOSED HYDRAULIC STRUCTURE Number, Size, Structure Type, (Additional Length)					
SILE	6-LANE WIDENING	8-LANE WIDENING	HYBRID 6-/8-LANE WIDENING			
3	Retain and extend 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC			
	(18' [RT]/47' [LT])	(25' [RT]/27' [LT])	(18' [RT]/47' [LT])			
4	Retain 2 @ 8' x 8' RCBC ; add supplemental pipe	Retain and extend 2 @ 8' x 8' RCBC; add supplemental pipe (45' [RT]/18' [LT])	Retain 2 @ 8' x 8' RCBC ; add supplemental pipe			
7	Retain and extend 3 @ 9' X 10' RCBC	Retain and extend 3 @ 9' X 10' RCBC	Retain and extend 3 @ 9' X 10' RCBC			
	(42' [RT]/20' [LT])	(42' [RT]/70' [LT])	(42' [RT]/20' [LT])			
10	Retain 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC (0' [RT]/8' [LT])	Retain 1 @ 6' x 6' RCBC			
11	Remove and replace Dual 3 - Span RC	Remove and replace Dual 3 - Span RC	Remove and replace Dual 3 - Span RC			
	Deck Bridges; L (Min) = 230'	Deck Bridges; L (Min) = 230'	Deck Bridges; L (Min) = 230'			
12	Retain and extend 1 @ 7' x 7' RCBC	Retain and extend 1 @ 7' x 7' RCBC	Retain and extend 1 @ 7' x 7' RCBC			
	(18' [RT]/0'[LT])	(26' [RT]/18' [LT])	(18' [RT]/0'[LT])			
13	Retain 3 @ 8' x 8' RCBC	Retain and extend 3 @ 8' x 8' RCBC; add supplemental pipe (32' [RT]/52' [LT])	Retain 3 @ 8' x 8' RCBC			
14	Retain and extend 2 @ 8' x 8' RCBC;	Retain and extend 2 @ 8' x 8' RCBC; add	Retain and extend 2 @ 8' x 8' RCBC;			
	add supplemental pipe	supplemental pipe	add supplemental pipe			
	(21' [RT]/16' [LT])	(33' [RT]/28' [LT])	(21' [RT]/16' [LT])			
16	Remove and replace Dual 3 - Span RC	Remove and replace Dual 3 - Span RC	Remove and replace Dual 3 - Span RC			
	Deck Bridges; L (Min) = 210'	Deck Bridges; L (Min) = 210'	Deck Bridges; L (Min) = 210'			
17	Retain and extend 3 @ 7' x 7' RCBC;	Retain and extend 3 @ 7' x 7' RCBC; add	Retain and extend 3 @ 7' x 7' RCBC;			
	add supplemental pipe	supplemental pipe	add supplemental pipe			
	(20' [RT]/30' [LT])	(36' [RT]/48' [LT])	(36' [RT]/48' [LT])			
18	Retain 1 @ 6' x 5' RCBC - 66" RCP w/ HW	Retain and extend 1 @ 6' x 5' RCBC - 66" RCP w/ HW (0' [RT]/8' [LT])	Retain and extend 1 @ 6' x 5' RCBC - 66" RCP w/ HW (0' [RT]/8' [LT])			
19	Retain and extend 1 @ 6' x 6' RCBC;	Retain and extend 1 @ 6' x 6' RCBC; add	Retain and extend 1 @ 6' x 6' RCBC;			
	add supplemental pipe	supplemental pipe	add supplemental pipe			
	(22' [RT]/27' [LT])	(48' [RT]/27' [LT])	(48' [RT]/27' [LT])			

Page 9 February 11, 2015


SITE	PROPOSED HYDRAULIC STRUCTURE Number, Size, Structure Type, (Additional Length)					
	6-LANE WIDENING	8-LANE WIDENING	HYBRID 6-/8-LANE WIDENING			
23	Retain and extend 2 @ 10' x 10' RCBC (28' [RT]/0' [LT])	Retain and extend 2 @ 10' x 10' RCBC (80' [RT]/24' [LT])	Retain and extend 2 @ 10' x 10' RCBC (80' [RT]/24' [LT])			
24	Retain 1 @ 8' x 8' RCBC	Retain 1 @ 8' x 8' RCBC	Retain 1 @ 8' x 8' RCBC			
25	Remove and replace Dual 6 - Span RC Deck Bridges; L (Min) = 460'	Remove and replace Dual 6 - Span RC Deck Bridges; L (Min) = 460'	Remove and replace Dual 6 - Span RC Deck Bridges; L (Min) = 460'			
26	Retain 1 @ 66" SPP w/ HW; 1 @ 14' x 14' RCBC (vehicle underpass)	Retain and extend 1 @ 66" SPP w/ HW; 1 @ 14' x 14' RCBC (vehicle underpass) (20' [RT]/40' [LT])	Retain and extend 1 @ 66" SPP w/ HW; 1 @ 14' x 14' RCBC (vehicle underpass) (20' [RT]/40' [LT])			


The Merger Team has concurred on this date of **February 11, 2015**, on the above proposed culvert and bridging recommendations for TIP Project I-4400/I-4700.


USACE	NCDOT
USEPA	USFWS
WRC	FHWA
DWR	SHPO
TVA	FBRMPO
EBCI	

APPENDIX A

TYPICAL ROADWAY SECTIONS










24:37 PM - Proj\14400-4700-rdy-1 ***|CFRNAMF***

R2 2'-6" CONCRETE CURB AND GUTTER








USE TYPICAL SECTION NO. 9 IN THE FOLLOWING LOCATIONS:

-Y2- SR1803 (CREST RD.)
-Y4- SR1793 (TRACEY GROVE RD.)
-Y5- SR1525 (DANA RD.)
-Y7- SR1503 (CLEAR CREEK RD.)
-Y8- SR1528 (BROOKSIDE CAMP RD.)
-Y9- SR1534 (NAPLES RD.)
-Y11- SR1345 (BUTLER BRIDGE RD.)
-Y12- SR3539 (FANNING BRIDGE RD.)



BRIDGE TYPICAL SECTION 1

RECONSTRUCTION
2 LANE SECTION

USE TYPICAL SECTION NO. 9 IN THE FOLLOWING LOCATIONS:

-Y2- SR1803 (CREST RD.) STA 18+50 TO STA 21+10
-Y4- SR1793 (TRACEY GROVE RD.) STA 21+30 TO STA 24+15
-Y5- SR1525 (DANA RD.) STA 34+80 TO STA 37+45
-Y7- SR1503 (CLEAR CREEK RD.) STA 19+05 TO STA 21+85
-Y8- SR1528 (BROOKSIDE CAMP RD.) STA 33+05 TO STA 35+70
-Y9- SR1534 (NAPLES RD.) STA 37+20 TO STA 40+05
-Y11- SR1345 (BUTLER BRIDGE RD.) STA 16+55 TO STA 19+00
-Y12- SR3539 (FANNING BRIDGE RD.) STA 21+75 TO STA 24+38

PAVEMENT SCHEDULE


A1 PROP. PORTLAND CEMENT CONCRETE PAVEMENT

C1 PROP. ASPHALT CONCRETE PAVEMENT

K PROP. SUBGRADE STABILIZATION


R1 DOUBLE FACED CONCRETE MEDIAN BARRIER


R2 2'-6" CONCRETE CURB AND GUTTER





APPENDIX B

SITE MAPS AND PHOTOGRAPHS











Looking at Upstream Face of 1 @ 6' x 6' RCBC under I-26



Looking Upstream from 1 @ 6' x 6' RCBC Inlet





Looking Inside of 1 @ 6' x 6' RCBC



Outlet of Drop Inlet Inside 1 @ 6' x 6' RCBC







Looking at Downstream Face of 1 @ 6' x 6' RCBC under I-26



Looking Downstream from 1 @ 6' x 6' RCBC Outlet








Map Projection:

North Carolina State Plane Projection Feet (Zone 3200) Datum: NAD 1983 (Horizontal), NAVD 1988 (Vertical)

1 inch = 500 feet 1:6,000





NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM

NORTH CAROLINA

PANEL 9588



Panel Contains:

COMMUNITY


HENDERSON COUNTY HENDERSONVILLE, CITY OF

PANEL SUFFIX 370125 370128

Site 4



MAP NUMBER 3700958800J MAP REVISED 10/2/2008



North Carolina State Plane Projection Feet (Zone 3200) Datum: NAD 1983 (Horizontal), NAVD 1988 (Vertical)

1 inch = 500 feet 1:6,000

0 250 500 1,000 Feet Meters 0 75 150 300



NORTH CAROLINA

NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM

PANEL 9587



Panel Contains:

COMMUNITY

HENDERSON COUNTY HENDERSONVILLE, CITY OF CID PANEL SUFFIX 370125 9587 J

370128

Site 4



MAP NUMBER 3700958700J MAP REVISED 10/2/2008



Looking at Upstream Face of 2 @ 8' x 8' RCBC under I-26



Looking at Upstream Left Ditch





Looking Upstream from 2 @ 8' x 8' RCBC Inlet



Looking Inside of Left Barrel





Looking Inside of Right Barrel



Crack in Right Barrel







Looking at Downstream Face of 2 @ 8' x 8' RCBC under I-26



Looking Downstream from 2 @ 8' x 8' RCBC Outlet







Map Projection:

North Carolina State Plane Projection Feet (Zone 3200) Datum: NAD 1983 (Horizontal), NAVD 1988 (Vertical)

1 inch = 500 feet 1:6,000

1,000 Feet 250 500 Meters 75 150 300



NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP **NORTH CAROLINA**

NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM

PANEL 9579



Panel Contains:

COMMUNITY

HENDERSON COUNTY HENDERSONVILLE, CITY OF

PANEL SUFFIX

370128

Site 7



MAP NUMBER 3700957900J MAP REVISED 10/2/2008



Looking at Upstream Face of 3 @ 9' x 10' RCBC under I-26



Looking Upstream from 3 @ 9' 10' RCBC Inlet





Looking Downstream in Left Barrel



Cracks in Left Barrel





Looking Downstream in Center Barrel







Damage on Downstream Center Barrel



Looking at Upstream Face of 3 @ 9' x 10' RCBC under I-26






Looking Downstream from 3 @ 9' x 10' RCBC Outlet



Looking Downstream







Looking at Upstream Face of 1 @ 6' x 6' RCBC under I-26



Looking Upstream from 1 @ 6' x 6' RCBC Inlet





Looking Upstream Inside of the Barrel



Looking Downstream Inside of the Barrel





Cracks on Downstream Side and Top Slab of the Barrel



Pipe Outlet on Right Side of the Barrel





Looking at Downstream Face of 1 @ 6' x 6' RCBC under I-26



Looking at Downstream Face of 1 @ 6' x 6' RCBC under I-26






Looking at Downstream Right Ditch



Looking Downstream from 1 @ 6' x 6' RCBC Outlet





Map Projection:

North Carolina State Plane Projection Feet (Zone 3200) Datum: NAD 1983 (Horizontal), NAVD 1988 (Vertical)

1 inch = 500 feet 1:6,000

0 250 500 1,000 Feet Meters 0 75 150 300



National Flood Insurance Program

NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

NORTH CAROLINA

PANEL 9670



Panel Contains:


COMMUNITY

HENDERSON COUNTY HENDERSONVILLE, CITY OF CID PANEL SUFFIX 370125 9670 J 370128 9670 J

Site 11



MAP NUMBER 3700967000J MAP REVISED 10/2/2008



Map Projection:

North Carolina State Plane Projection Feet (Zone 3200) Datum: NAD 1983 (Horizontal), NAVD 1988 (Vertical)

1 inch = 500 feet

250 500 1,000 Feet Meters 75 150 300



1:6,000

National Flood Insurance Program

NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

NORTH CAROLINA

PANEL 9579



Panel Contains:

COMMUNITY

HENDERSON COUNTY HENDERSONVILLE, CITY OF

PANEL SUFFIX 370128 9579

Site 11



MAP NUMBER 3700957900J MAP REVISED 10/2/2008



Looking at Upstream Face



Looking at Downstream Face






Looking Downstream



Looking Upstream







Looking at Upstream Face of 1 @ 7' x 7' RCBC under I-26



Looking Upstream from 1 @ 7' x 7' RCBC Inlet





Looking at Upstream Channel coming from the right



Looking at Upstream Channel coming from the right






Looking at Upstream Channel coming from the left



Looking Downstream inside of the Barrel





Cracks on the Side of the Wall Inside of the Barrel



Cracks on the Top Slab Inside of the Barrel





Looking Downstream inside of the Barrel



Looking at Downstream Face of 1 @ 7' x 7' RCBC under I-26





Looking Downstream from 1 @ 7' x 7' RCBC Outlet



Upstream Face of Downstream 54" CMP with Rock Headwall







Downstream Face of Downstream 54" CMP with Rock Headwall



Downstream of 54" CMP with Rock Headwall









Looking at Upstream Face of 3 @ 8' x 8' RCBC under I-26



Looking Upstream from 3 @ 8' x 8' RCBC Inlet





Looking Downstream in Left Barrel



Crack in the Top Slab of Left Barrel





Looking Upstream in Center Barrel



Looking Upstream in Right Barrel





Drop Inlet in Center Barrel



Looking at Downstream Face of 3 @ 8' x 8' RCBC under I-26





Looking Downstream from 3 @ 8'x 8' RCBC Outlet



Looking at Upstream Face of 78" CMP






Looking at Downstream Face of 78" CMP



Erosion on top of 78" CMP







Looking at Upstream Face of 2 @ 8' x 8' RCBC under I-26



Looking Upstream from 2 @ 8' x 8' RCBC





Looking Downstream in Left Barrel



Looking Downstream in Right Barrel






Looking at Downstream Face of 2 @ 8' x 8' RCBC under I-26



Looking Downstream from 2 @ 8' x 8' RCBC







Looking at Upstream Face



Looking Upstream







Looking at Downstream Face



Looking Downstream









Looking at Upstream Face of 3 @ 7' x 7' RCBC under I-26



Looking Upstream of 3 @ 7' x 7' RCBC





Looking Downstream in Left Barrel



Looking Downstream in Center Barrel





Looking Upstream in Right Barrel



Looking at Downstream Face of 3 @ 7' x 7' RCBC






Looking at Downstream Face of 3 @ 7' x 7' RCBC under I-26



Looking Downstream of 3 @ 7' x 7' RCBC







Looking at Upstream Face of 1 @ 6' x 5' RCBC under Airport Rd.



Looking Upstream from 1 @ 6' x 5' RCBC Inlet





Pipe located Upstream of 1 @ 6' x 5' RCBC



Looking Downstream Inside 1 @ 6' x 5' RCBC





Looking Downstream Inside of 66" RCP



Looking at Downstream Face of 66" RCP with Headwall under Airport Rd.






Looking Downstream from 66" RCP



Looking Downstream 66" RCP







Looking at Upstream Face of 1 @ 6' x 6' RCBC under I-26



Looking Upstream from 1 @ 6' x 6' RCBC Inlet





Looking Downstream Inside of 1 @ 6' x 6' RCBC



Looking Upstream of 1 @ 6' x 6' RCBC





Looking at Downstream Face of 1 @ 6' x 6' RCBC under I-26



Looking at Downstream Face of 1 @ 6' x 6' RCBC under I-26





Looking at Upstream Face of 1 @ 6' x 6' RCBC under Hidden Creek Rd



Looking at Downstream Face of 1 @ 6' x 6' RCBC under Hidden Creek Rd






Looking Downstream from Hidden Creek Rd



Home Downstream of Hidden Creek Rd







Looking at Upstream Face of 2 @ 10' x 10' RCBC under I-26




Looking Upstream from 2 @ 10' x 10' RCBC Inlet





Looking Downstream in Left Box



Looking Upstream in Left Box





Looking Downstream in Right Box



Looking Upstream in Right Box






Looking at Downstream Face of 2 @ 10' x 10' RCBC under I-26



Looking Downstream from 2 @ 10' x 10' RCBC Outlet







Looking at Upstream Face of 1 @ 8' x 8' RCBC under I-26



Looking Upstream from 1 @ 8' x 8' RCBC Inlet





Looking Downstream



Looking Upstream





Pipe Outlet in the Middle of the Box



Crack in the Top Slab





Cracks in the Box



Right Headwall Separation on the Downstream Side






Looking at Downstream Face of 1 @ 8' x 8' RCBC under I-26



Looking Downstream from 1 @ 8' x 8' RCBC Outlet







Looking Upstream



Looking Upstream






Looking at Downstream Face



Looking Downstream







Looking at Upstream Face of 66" SPP with Headwall under I-26



Upstream Stormwater Pond





Looking Downstream Inside of 66" SPP



Looking at Downstream Face of 66" SPP with Headwall under I-26





Looking Downstream of 66" SPP



Upstream Side of Vehicular Underpass





Downstream Side of Vehicular Underpass



Looking Downstream from Vehicular Underpass



Final Meeting Summary



Project: STIP Project I-4400/I-4700 (I-26 Widening)

Subject: Merger Process Concurrence Point 2A

Meeting Date, Time: 2/11/15, 3:15 PM

Meeting Location: NCDOT Century Center, Building B, Hydraulics Conference Room

Present:

Name	Organization	Email Address
Mitch Batuzich	FHWA, NC	Michael.batuzich@dot.gov
Lori Beckwith	USACE	loretta.a.beckwith@usace.army.mil
Steve Kichefski	USACE	Steven.l.kichefski@usace.army.mil
Cynthia Van Der Wiele	USEPA	vanderwiele.cynthia@epa.gov
Marella Buncick	USFWS	marella buncick@fws.gov
Marla Chambers	NCWRC	marla.chambers@ncwildlife.org
Paul Black*	French Broad River MPO	paul@landofsky.org
Ricky Tipton	NCDOT, Division 13	rtipton@ncdot.gov
Bill Zerman	NCDOT, Hydraulics	bzerman@ncdot.gov
Jennifer Harris	NCDOT, PDEA	Jhharris1@ncdot.gov
Undrea Major	NCDOT, PDEA	ujmajor@ncdot.gov
Zahid Baloch	NCDOT, PDEA	zbaloch@ncdot.gov
Bill Barrett	NCDOT, PDEA, NES	wabarrett@ncdot.gov
Carla Dagnino	NCDOT, PDEA, NES	cdagnino@ncdot.gov
Kevin Moore	NCDOT, Roadway	kmoore@ncdot.gov
Steve Kendall	NCDOT, Roadway	sdkendall@ncdot.gov
Wael Arafat	NCDOT, Structures	warafat@ncdot.gov
Pam Cook	NCDOT, TPB	prcook@ncdot.gov
Brendan Merithew	NCDOT, TPB	bwmerithew@ncdot.gov
Mark Staley	NCDOT, REU	mstaley@ncdot.gov
Kiersten Bass	HNTB	kbass@hntb.com
Jamie Byrd	HNTB	jabyrd@hntb.com
Eric Seckinger*	HNTB	eseckinger@hntb.com
Jonathan Williamson*	HNTB	jewilliamson@hntb.com

^{*}Participated via telephone

Summary: A meeting was held on February 11, 2015, to discuss and reach concurrence on Merger Process Concurrence Point 2A (Bridging Decisions and Alignment Review) for STIP Project I-4400/I-4700 (I-26 Widening). NCDOT distributed, on December 23, 2014, an informational packet to the participating agencies and team members for their review prior to the meeting. Dre Major began the meeting with a brief summary of the purpose of the meeting, and introductions were made by each member of the group present or participating via telephone. Kiersten Bass then provided a PowerPoint presentation (attached). She covered the purpose of the meeting, the project's location and background, including previous agency concurrences obtained for CP1 and CP2 in June 2013. The presentation was turned over to Jamie Byrd, who presented data relevant to CP2A (existing drainage crossings and drainage structure recommendations).

The following summarizes the general topics discussed:

1. For roadway construction on new location, three-cell box culverts are not typically used. For purposes of widening of an existing facility, and specifically for this project, all multi-barrel box culverts should have their

Meeting Summary - STIP I-4400/4700 I-26 Widening 02/11/15 (cont'd)

flows restricted to the number of cells that most closely matches the natural stream conditions in order to maintain normal stream flow widths and depths.

- Sills should be used in multi-cell box culverts to route the base flow into the appropriate number of cells.
- When sills are used, floodplain benches should be constructed to route flows into the active normal flow cell(s).
- 2. Existing box culvert conditions.
 - The Hydraulic Tech Memo contains a visual assessment of the existing conditions.
 - The conditions of structures greater than 20 feet in width have Inspection Reports with detailed condition assessments.
- 3. Perched stream conditions should be corrected at all locations as part of the project.
- 4. Mitigation costs should be included in the cost comparison for a more accurate comparison of total costs.
 - Table 1, Recommended Major Drainage Structures, included in the meeting material notes "Stream mitigation is not included in the culvert extension costs. However, a 2:1 mitigation ratio would result in an increase in the culvert extension cost by \$762/If." After the jurisdictional site visit with the Agencies, the Preliminary Jurisdictional Determination (PJD) was updated to reflect the final stream calls and mitigation ratios that will be required at permitting. This is included in the PJD dated July 22, 2014 and has been used to update Table 1 of the CP2A meeting packet (attached).

The following summarizes the site-specific discussions:

Site 3 – Why are the potential stream impacts less for the 8-lane alternative as compared to the 6-lane and Hybrid alternatives?

• At this location, the 8-lane Alternative typical section used proposed guardrail with a fill slope of 2:1 and the 6-lane Alternative used no guardrail with a fill slope of 4:1. This difference made the footprint larger for the 6-lane Alternative than the 8-lane Alternative. HNTB will revise the typical section to eliminate the guardrail for the 6-lane Alternative and will correct Table 1 to reflect the change in potential stream impacts.

Site 4 – Marella identified this crossing as a candidate for a bridge since a supplemental pipe was recommended for all alternatives.

- HNTB advised that Dunn Creek is a FEMA regulated stream and would need to meet FEMA backwater criteria.
- HNTB added that with a drainage area of 2.58sq. mi., this crossing would generally not be considered for a bridge crossing.

Site 7 – Marella and Marla identified this crossing as a candidate for a bridge since it is a 3-cell box culvert with some internal cracks and over widening of the channel at the inlet.

- HNTB advised that Devils Fork is a FEMA regulated stream and would need to meet FEMA backwater criteria.
- HNTB added that with a drainage area of 6.8sq. mi., this crossing may be considered for a bridge crossing for new location design, but does not recommend a bridge for an existing facility.
- For preliminary design of the Preferred Alternative, HNTB will review the Inspection Report for the crossing.

Meeting Summary - STIP I-4400/4700 I-26 Widening 02/11/15 (cont'd)

Site 13 - Marella and Marla felt that this crossing was a candidate for a bridge since it is a 3-cell box culvert.

- Marella also expressed concern about a direct stormwater discharge through the culvert top slab.
- HNTB advised that Featherstone Creek is a FEMA regulated stream and would need to meet FEMA backwater criteria.
- HNTB added that with a drainage area of 4.1sq. mi., this crossing would generally not be considered for a bridge crossing.

Site 17 – In accordance with previous comments for 3-cell box culverts, any improvements at this site should include sills and flood plain benches.

Site 23 – After discussing this crossing with respect to its location to Lake Julian and the French Broad River, the group agreed that this site did not warrant special consideration.

The Merger Team agreed with the recommendations identified in the table included in the Merger Project Team Agreement Signature Form, except it was requested that for the 8-lane Alternative, bridges be evaluated for Sites 4 and 7. As such, the signature form was revised to include *Evaluate bridges at Sites 4 and 7 for the 8-lane Alternative.

Action Items:

- PDEA, NES will provide the PJD mitigation ratios for estimating the mitigation cost associated with proposed culvert extensions. [completed]
- HNTB will update Table 1, Recommended Major Drainage Structures, to include stream mitigation costs for the proposed culvert extensions. [completed]
- HNTB will eliminate the guardrail and associated slope for the 6-lane Alternative and update Table 1 to reflect the change in potential stream impacts. [completed]

Attachments:

• Updated Table 1 from CP2A packet, signed Concurrence Point Number 2A form, meeting agenda and presentation.

4. MERGER PROJECT TEAM AGREEMENT SIGNATURE FORM

Merger Project Team Agreement

Concurrence Point 2A: Bridging Decisions and Alignment Review

Project Name/Description:
I-26, Widen from US 25 in Hendersonville in Henderson County to
I-40/I-240 in Buncombe County
TIP Project: I-4400/I-4700

Bridging Decisions: Based on the current preliminary hydraulics design for the existing major drainage structures for TIP Project I-4400/I-4700, the proposed culvert and bridging recommendations are presented in the following table:

		PROPOSED HYDRAULIC STRUCTURE										
SITE	Number, Size, Structure Type, (Additional Length)											
	6-LANE WIDENING	8-LANE WIDENING	HYBRID 6-/8-LANE WIDENING									
3	Retain and extend 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC									
J	(18' [RT]/47' [LT])	(25' [RT]/27' [LT])	(18' (RT)/47' (LT))									
4*	Retain 2 @ 8' x 8' RCBC ; add supplemental pipe	Retain and extend 2 @ 8' x 8' RCBC; add supplemental pipe (45' [RT]/18' (LT])	Retain 2 @ 8' x 8' RCBC ; add supplemental pipe									
7*	Retain and extend 3 @ 9' X 10' RCBC (42' [RT]/20' [LT])	Retain and extend 3 @ 9' X 10' RCBC (42' [RT]/70' [LT])	Retain and extend 3 @ 9' X 10' RCBC (42' [RT]/20' [LT])									
10	Retain 1 @ 6' x 6' RCBC	Retain and extend 1 @ 6' x 6' RCBC (0' (RT)/8' (LT))	Retain 1 @ 6' x 6' RCBC									
11	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 230'	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 230'	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 230'									
12	Retain and extend 1 @ 7' x 7' RCBC (18' (RT)/0'(LT))	Retain and extend 1 @ 7' x 7' RCBC (26' [RT]/18' [LT])	Retain and extend 1 @ 7' x 7' RCBC (18' [RT]/0'[LT])									
13	Retain 3 @ 8' x 8' RCBC	Retain and extend 3 @ 8' x 8' RCBC; add supplemental pipe (32' [RT]/52' [LT])	Retain 3 @ 8' x 8' RCBC									
14	Retain and extend 2 @ 8' x 8' RCBC; add supplemental pipe (21' [RT]/16' [LT])	Retain and extend 2 @ 8' x 8' RCBC; add supplemental pipe (33' [RT]/28' [LT])	Retain and extend 2 @ 8' x 8' RCBC; add supplemental pipe (21' [RT]/16' [LT])									
16	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 210'	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 210'	Remove and replace Dual 3 - Span RC Deck Bridges; L (Min) = 210'									
17	Retain and extend 3 @ 7' x 7' RCBC; add supplemental pipe (20' [RT]/30' [LT])	Retain and extend 3 @ 7' x 7' RCBC; add supplemental pipe (36' [RT]/48' (LT])	Retain and extend 3 @ 7' x 7' RCBC; add supplemental pipe (36' [RT]/48' [LT])									
18	Retain 1 @ 6' x 5' RCBC - 66" RCP w/ HW	Retain and extend 1 @ 6' x 5' RCBC - 66" RCP w/ HW (0' [RT]/8' [LT])	Retain and extend 1 @ 6' x 5' RCBC - 66" RCP w/ HW (0' [RT]/8' (LT])									
19	Retain and extend 1 @ 6' x 6' RCBC; add supplemental pipe (22' [RT]/27' [LT])	Retain and extend 1 @ 6' x 6' RCBC; add supplemental pipe (48' [RT]/27' [LT])	Retain and extend 1 @ 6' x 6' RCBC; add supplemental pipe (48' [RT]/27' [LT])									

SITE	PROPOSED HYDRAULIC STRUCTURE Number, Size, Structure Type, (Additional Length)									
	6-LANE WIDENING	8-LANE WIDENING	HYBRID 6:/8-LANE WIDENING							
23	Retain and extend 2 @ 10' x 10' RCBC (28' (RT)/0' (LT))	Retain and extend 2:@ 10" x 10" RCBC (80" [RT]/24" [LT])	Retain and extend 2 @ 10' x 10' ACBC (80' [RT]/24' (LT))							
24	Retein 1 @ 8' x 8' RCBC	Retain 1 @ 8' x 8' RCBC	Retain 1 @ 8' x 8' RCBC							
25	Remove and replace Dual 6 - Span RC Deck Bridges; E (Min) = 460	Remove and replace Qual 6 - Span RC Deck Bridges J. (Min) = 460	Remove and replace Dual 6 - Span RC Deck Bridges; L (Min) = 460							
26	Retain 1 @ 66" SPP w/ HW; 1 @ 14" x 14" RCBC (vehicle underpass)	Retain and extend 1 @ 66" SPP w/ HW; 1 @ 14" x 14" RCBC (Vehicle underpass) (20" [RT]/40" [LT])	Retain and extend 1:@ 66" SPP w/ HW; 1:@ 14'x 14"RCBC (vehicle Underpass) (20" (RT)/40" (LT))							

^{*}Evaluate bridges at Sites 4 and 7 for the 8-Lane Alternative.

The Merger Team has concurred on this date of February 11, 2015; on the above proposed culvert and bridging recommendations for TIP Project I-4400/I-4700.

	^		All Property of the Control of the C	
USACE TOM A	Beethuit-	NCDOT /	Indroa Wa	i IoL
	1 1 1			*
high this	t landeru	Jacobs =	<i>1 l.</i> b-	erve
WRC Marla	L. CanDer W USEFA Clambus	_ FHWA _	uted I Ta	T., E/1
DWR Kens				
DWR	VEVV		$\bigcap_{\lambda} A = \bigcap_{\lambda} A$	x-cana
TVA		FBRMPO	128B	\mathbb{Z}^{\prime}
EBCI	• •	17 15 基本的	1.0	·

					STREAM IN	NFORMA	TION				EXISTING STRUCTURE	6-LANE WIDENING			8-LANE WIDENING			HYBRID 6-/8-LANE WIDENING		
SITE NUMBER	STATION	ROUTE	STREAM NAME	NRTR MAP ID	NCDWR STREAM INDEX NUMBER	MITIGATION	PERENNIAL / INTERMITTENT	STREAM LENGTH (ft)	STREAM CLASS	DRAINAGE AREA (sq mi) [acres]	Number, Size, Structure Type (Existing Length)	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (lf)/ Wetland (ac) Impact	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (If)/ Wetland (ac) Impact	Recommended Structure (Additional Length)	Cost Estimate - Culvert Extension (Bridge)	Potential Stream (If)/ Wetland (ac) Impact
3	-L- 79+09	I-26	UT to Dunn Creek	SV	6-55-8- 1-1	2:1	Р	725	С	0.28 178	1 @ 6' x 6' RCBC (240')	Retain and extend (18' [RT]/0' [LT])	\$100,000 (\$1,573,000)	58/0	Retain and extend (25' [RT]/27' [LT])	\$145,000 (\$1,808,000)	132/0	Retain and extend (18' [RT]/0' [LT])	\$100,000 (\$1,573,000)	58/0
4	-L- 90+32	I-26	Dunn Creek	ST	6-55-8- 1-1	2:1	Р	845	С	2.58 1,649	2 @ 8' x 8' RCBC (354')	Retain existing; add supplemental pipe	\$248,000 (\$1,501,000)	0/0	Retain and extend; add supplemental pipe (45' [RT]/18' [LT])	\$491,000 (\$1,677,000)	143/0	Retain existing; add supplemental pipe	\$248,000 (\$1,501,000)	0/0
7	-L- 208+70	I-26	Devils Fork	SAJ	6-55-8-2	2:1	Р	2849	С	6.80 4,351	3 @ 9' X 10' RCBC (220')	Retain and extend (42' [RT]/20' [LT])	\$285,000 (\$1,645,000)	142/0	Retain and extend (42' [RT]/70' [LT])	\$466,000 (\$1,894,000)	192/0	Retain and extend (42' [RT]/20' [LT])	\$285,000 (\$1,645,000)	142/0
10	-L- 248+18	I-26	UT to Devils Fork	SAR	6-55-8-2	EAST 2:1 WEST 1:1	Р	812	С	0.29 185	1 @ 6' x 6' RCBC (382')	Retain existing	0	0/0	Retain and extend (0' [RT]/8' [LT])	\$25,000 (\$1,722,000)	48/0	Retain existing	0	0/0
11	-L- 334+69	I-26	Clear Creek	SBD	6-55-11- (5)	2:1	Р	908	С	44.30 28,352	Dual 3 - Span RC Deck Bridges; L = 220.14'	Remove and replace; L (Min) = 230'	(\$3,577,000)	-	Remove and replace; L (Min) = 230'	(\$4,212,000)	-	Remove and replace; L (Min) = 230'	(\$3,577,000)	-
12	-L- 407+69	I-26	UT to Mud Creek	SBG	6-55	1:1	Р	1,433	С	0.46 296	1 @ 7' x 7' RCBC (266')	Retain and extend (18' [RT]/0'[LT])	\$40,000 (\$2,436,000)	58/0	Retain and extend (26' [RT]/18' [LT])	\$91,000 (\$2,836,000)	124/0	Retain and extend (18' [RT]/0'[LT])	\$40,000 (\$2,436,000)	58/0
13	-L- 438+81	I-26	Featherstone Creek	SBP	6-55-12	2:1	Р	643	С	4.09 2,616	3 @ 8' x 8' RCBC (160')	Retain existing	0	0/0	Retain and extend; add supplemental pipe (32' [RT]/52' [LT])	\$476,000 (\$1,293,000)	164/0	Retain existing	0	0/0
14	-L- 500+94	I-26	Byers Creek	SBU	6-55-13	2:1	Р	1219	С	2.42 1,550	2 @ 8' x 8' RCBC (156')	Retain and extend; add supplemental pipe (21' [RT]/16' [LT])	\$285,000 (\$1,070,000)	117/0	Retain and extend; add supplemental pipe (33' [RT]/28' [LT])	\$367,000 (\$1,208,000)	141/0	Retain and extend; add supplemental pipe (21' [RT]/16' [LT])	\$285,000 (\$1,070,000)	117/0
16	-L- 669+02	I-26	Cane Creek	SCW	6-57-(9)	2:1	Р	878	С	83.80 53,632	Dual 3 - Span RC Deck Bridges; L = 198.25'	Remove and replace; L (Min) = 210'	(\$3,297,000)	-	Remove and replace; L (Min) = 210'	(\$3,876,000)	-	Remove and replace; L (Min) = 210'	(\$3,876,000)	-
17	-L- 682+68	I-26	Kimsey Creek	SCY	6-57-22	2:1	Р	960	С	2.49 1,594	3 @ 7' x 7' RCBC (236')	Retain and extend; add supplemental pipe (20' [RT]/30' [LT])	\$386,000 (\$1,861,000)	130/0	Retain and extend; add supplemental pipe (36' [RT]/48' [LT])	\$521,000 (\$2,151,000)	164/0	Retain and extend; add supplemental pipe (36' [RT]/48' [LT])	\$521,000 (\$2,151,000)	164/0
18	-Y12- 11+44	SR 1358	UT to French Broad River	-	6-(54.5)	-	-	-	В	0.14 88	1 @ 6' x 5' RCBC - 66" RCP w/ HW (540')	Retain existing	0	0/0	Retain and extend (0' [RT]/8' [LT])	\$43,000	48/0	Retain and extend (0' [RT]/8' [LT])	\$43,000	48/0
19	-L- 800+81	I-26	UT to French Broad River	SDC	6-(54.5)	2:1	Р	961	В	0.36 228	1 @ 6' x 6' RCBC (220')	Retain and extend; add supplemental pipe (22' [RT]/27' [LT])	\$331,000 (\$1,933,000)	129/0	Retain and extend; add supplemental pipe (48' [RT]/27' [LT])	\$380,000 (\$2,236,000)	155/0	Retain and extend; add supplemental pipe (48' [RT]/27' [LT])	\$380,000 (\$2,236,000)	155/0
23	-L47001- 897+06	I-26	Powell Creek	SDN	6-62	2:1	Р	470	С	5.06 3,240	2 @ 10' x 10' RCBC (264')	Retain and extend (28' [RT]/0' [LT])	\$119,000 (\$2,005,000)	68/0	Retain and extend (80' [RT]/24' [LT])	\$390,000 (\$2,322,000)	184/0	Retain and extend (80' [RT]/24' [LT])	\$390,000 (\$2,322,000)	184/0
24	-L47001- 931+91	I-26	Ducker Creek	SDT	6-63	2:1	Р	377	С	0.99 632	1 @ 8' x 8' RCBC (552')	Retain existing	0	0/0	Retain existing	0	0/0	Retain existing	0	0/0
25	-L47002- 1076+40	I-26	French Broad River		6-(54.5)	-	-	-	В	678.00 433,920	Dual 6 - Span RC Deck Bridges; L1 = 440.9' L2 = 453.4'	Remove and replace; L (Min) = 460'	(\$6,804,000)	-	Remove and replace; L (Min) = 460'	(\$8,074,000)	-	Remove and replace; L (Min) = 460'	(\$8,074,000)	-
26	-L47002- 1151+85	I-26	Long Valley Branch	SFN	6-75	1:1	Р	44	С	0.25 158	1 @ 66" SPP w/ HW; 1 @ 14' x 14' RCBC [vehicle underpass] (220')	Retain existing	0	0/0	Retain and extend (20' [RT]/40' [LT])	\$171,000 (\$2,665,000)	140/0.25	Retain and extend (20' [RT]/40' [LT])	\$171,000 (\$2,665,000)	140/0.25

NOTES: Minimum supplemental pipe size is 48".

Stream/wetland impacts are measured from the openings of the existing culverts to 40 feet beyond slope stakes.

For comparison, costs to replace existing culverts with bridges were estimated for sites where culvert extensions would be needed. Contour mapping was used to estimate the length of bridges at sites with existing culverts.

Cost estimates are based on unit costs and bid averages provided by NCDOT.

Unit costs

Culvert: single -\$35/sf, double - \$30/sf, triple - \$25/sf

Bridges: \$115/sf

48" Supplemental Pipe: \$620/If (bore and jack)

Stream mitigation cost is included in the culvert extension estimate and was calculated using mitigation ratio information from Table 1 in the Preliminary Jurisdictional Determination report (July 2014); with the basis that a 2:1 mitigation ratio would result in an increase in the culvert extension cost by \$782/If and a 1:1 mitigation ratio would result in an increase in the culvert extension cost by \$381/If.

On-site detour cost was included in the replace existing culverts with bridges estimate and was calculated using the basis of 3,100sy of temporary pavement per traffic shift during construction of each of the new dual bridges. Barrier and earthwork costs were also included to arrive at a total estimate of \$350,000 per culvert to bridge replacement.

Site 18 is outside the NRTR boundary.

Wetlands are present only at Site 26.



CONCURRENCE POINT 2A NEPA/404 MERGER TEAM MEETING



STIP Project I-4400/I-4700 Improve I-26 from US 25 to I-40 (Buncombe and Henderson Counties)

February 11, 2015

MEETING AGENDA

I. Introduction

- Purpose of Today's Meeting
- Project Location
- Project Schedule

Meeting Material Tabs

- Recommended Major Drainage Structures Table
 - Merger Project Team Signature Form
- 2. Site Maps and Photographs

II. Merger Team Concurrences to Date

- CP1 Project Purpose and Need
- CP2 Alternatives to be Studied in Detail

III. Merger Concurrence Point 2A

- Existing Drainage Crossings
- Drainage Structure Recommendations
- Discussion
- Concurrence on Hydraulic Recommendations with Signatures



Bridging Decisions &



Alignment Review for I-26

From US 25 in Hendersonville in Henderson County to I-40/I-240 in Buncombe County

STIP Project I-4400/I-4700

SECTION 404 / NEPA
INTERAGENCY MEETING FOR
MERGER CONCURRENCE POINT 2A

February 11, 2015



