DESIGN PUBLIC MEETING MAP

PROJECT P-5740
STATE PROJECT 48156.1.1
F.A#: FR-CRS-18-004-062649
NEW HANOVER COUNTY
BRUNSWICK COUNTY
BELTLINE RAILROAD IMPROVEMENTS
FROM DAVIS YARD TO 3RD STREET
ROLL 1 OF 2 FEBRUARY 2020

BEGIN TIP PROJECT P-5740
-L1- DAVIS YARD

TO LUMBERTON

DAVIS YARD

CAPE FEAR RIVER

BRUNSWICK COUNTY

NEW HANOVER COUNTY

CEDAR HILL DRIVE

UPGRADE NAVASSA DRAW BRIDGE MP SE 360.8

UPGRADE BRIDGE MP SE 361.1

UPGRADE BRIDGE MP SE 361.3

-L1-

CSX TRANSPORTATION

UPGRADE BRIDGE MP SE 361.9

US-421

UPGRADE HILTON DRAW BRIDGE MP SE 363.1

NORTHEAST CAPE FEAR RIVER

WILMINGTON CITY LIMITS

CORNELIUS HARNETT DRIVE

US-74 /MARTIN LUTHER KING JR PARKWAY

REALIGN CURVE MP SE 363.9-ACB 244.2

-L1-

-L1-

SMITH CREEK

UPGRADE BRIDGE MP ACB 244.7

SEE INSET 'A'

KING STREET

23RD STREET

CSX TRANSPORTATION

-L2-

30TH STREET

PRINCESS PLACE DRIVE

CLAY STREET

HENRY STREET

MARKET STREET

SEE INSET 'B'

-L2-

MARKET STREET

11TH STREET

UPGRADE BRIDGE MP ACB 247.7

FOREST HILL DRIVE

COLONIAL DRIVE

WRIGHTSVILLE AVENUE

COVIL AVENUE

MERCER AVENUE

OLEANDER AVENUE

17TH STREET

16TH STREET

-L2-

CSX TRANSPORTATION

MARSTELLAR STREET

13TH STREET

5TH STREET

HOOPER STREET

4TH STREET

SEE INSET 'C'

TO PORT OF WILMINGTON

12TH STREET

10TH STREET

9TH STREET

8TH STREET

7TH STREET

6TH STREET

END TIP PROJECT P-5740
-L2- 3RD STREET

NAD 83

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION
INCOMPLETE PLANS
DO NOT USE FOR RIGHT OF WAY ACQUISITION

600' 0' 600' 1200'
300'
(ENGLISH)

LEGEND

- BRIDGES
- PROPOSED EDGE OF PAVEMENT
- CROSSING SIGNAL UPGRADES
- CROSSING MEDIAN/SIDEWALK INSTALLATION
- CROSSING CLOSURE
- EXISTING RAILROAD RIGHT OF WAY
- COUNTY LINES
- CITY AND TOWN LINES

LEGEND

- BRIDGES
- PROPOSED EDGE OF PAVEMENT
- CROSSING SIGNAL UPGRADES
- CROSSING MEDIAN/SIDEWALK INSTALLATION
- CROSSING CLOSURE
- EXISTING RAILROAD RIGHT OF WAY
- COUNTY LINES
- CITY AND TOWN LINES

CROSSING IMPROVEMENT KEY

4TH STREET – INSTALL GATES
HOOPER STREET – CLOSE CROSSING
5TH STREET – EXTEND MEDIAN
6TH STREET – INSTALL FLASHERS
7TH STREET – INSTALL FLASHERS
8TH STREET – INSTALL FLASHERS
9TH STREET – CLOSE CROSSING
10TH STREET – INSTALL FLASHERS
12TH STREET – INSTALL FLASHERS
13TH STREET – INSTALL GATES
MARSTELLAR STREET – INSTALL MEDIAN
16TH STREET – UPGRADE SIDEWALKS
17TH STREET – UPGRADE SIDEWALKS
OLEANDER DRIVE – UPGRADE FLASHERS AND INSTALL MEDIAN
WRIGHTSVILLE AVENUE – UPGRADE SIGNAL
COLONIAL DRIVE – INSTALL GATES
FOREST HILLS DRIVE – INSTALL GATES
MERCER AVENUE – INSTALL GATES
COVIL AVENUE – UPGRADE FLASHERS
MARKET STREET – INSTALL MEDIAN
HENRY STREET – UPGRADE FLASHERS
CLAY STREET – CLOSE CROSSING
PRINCESS PLACE DRIVE – UPGRADE FLASHERS AND SIDEWALKS
30TH STREET – INSTALL GATES
23RD STREET – INSTALL MEDIAN
KING STREET – INSTALL FLASHERS AND GATES. MODIFY STREET ALIGNMENT.

DESIGN PUBLIC MEETING MAP
PROJECT P-5740
STATE PROJECT 48156.1.1
F.A#: FR-CRS-18-004-062649
NEW HANOVER COUNTY
BRUNSWICK COUNTY
BELTLINE RAILROAD IMPROVEMENTS
FROM DAVIS YARD TO 3RD STREET
ROLL 1 OF 2 FEBRUARY 2020